



LONGITUDINAL SECTION A-A

SCALE 1:50




PLAN VIEW

SCALE 1:100



INLET ELEVATION

SCALE 1:50




DETAIL J

SCALE 1:25



DETAIL H


SCALE 1:10



DETAIL G

WEEPHOLE DETAIL

SCALE 1:10



SECTION F-F

SCALE 1:50

HYDRAULIC INFORMATION CULVERT 10473	
EFFECTIVE CATCHMENT AREA (Km ²)	3,277
DESIGN FLOOD (m/s)	2,0
DESIGN FLOOD Q (m ³ /s)	8,303
HYDROLOGICAL METHOD	RATIONAL METHOD ALTERNATIVE 3
STREAM AVERAGE SLOPE (m/m)	5,8
DESIGN FLOW VELOCITY (m/s)	0,726
LEVEL OF Q _d AND LEVEL OF SBP (m)	110,052 - 113,518
FREEBOARD AT CULVERT	FREEBOARD LEVEL DICTATED BY ROAD GEOMETRY

- GENERAL NOTES:**
- THE CULVERTS ARE DESIGNED ACCORDING TO TMH7 PARTS 1-3 CODE OF PRACTICE FOR THE DESIGN OF HIGHWAY BRIDGES AND CULVERTS IN SOUTH AFRICA, AS AMENDED IN 1988.
 - SINGLE CAST INSITU PORTAL CULVERT WITH 1:5 BATTER 4461mm X 3400mm
 - FILL HEIGHTS
 - MIN FILL HEIGHT = 380 mm
 - MAX FILL HEIGHT = 780 mm
 - DESIGN TABLE (WCS/60/4/D3)
 - FILL HEIGHT = 500 mm
 - DESIGN SPAN = 4500 mm
- DESIGN LOADING AND CONDITIONS ON CULVERTS:**
- PRIMARY TRAFFIC LOADING ON CULVERTS (TMH7 PART 2 - 2.6.6):
 - (1) NA LOADING
 - (2) NB 36 LOADING
 - (3) NC LOADING
 - VERTICAL EARTH LOADING ON CULVERTS (TMH7 PART 2 - 2.3.3)
 - (1) FILL HEIGHT VARIES FROM 0 TO 6 METERS ABOVE TOP OF CULVERT
 - HORIZONTAL EARTH PRESSURE ON CULVERTS (TMH7 PART 2 - 2.4):
 - (1) SOIL TYPE I - 5.6 kN/m² PER METER DEPTH
 - (2) SOIL TYPE II - 7.8 kN/m² PER METER DEPTH
 - (3) SURCHARGE PRESSURE OF NA, NB36 AND NC HIGHWAY TRAFFIC LOADING
 - (4) NO ALLOWANCE WAS MADE FOR HORIZONTAL WATER PRESSURE BEHIND THE WALLS AND SHOULD BE RELIEVED BY MEANS OF A PROPER DRAINAGE SYSTEM AND WEEPHOLES.
 - MATERIAL DENSITIES:
 - (1) SOIL = 2000 kg/m³
 - (1) CONCRETE = 2600 kg/m³
 - FOUNDING CONDITIONS:
 - (1) CULVERTS WERE DESIGNED BOTH FOR YIELDING AND UNYIELDING FOUNDATION CONDITIONS.
 - (2) UNSUITABLE FOUNDING MATERIAL SHALL BE REPLACED WITH COMPACTED GRANULAR MATERIAL MASS CONCRETE UP TO MINIMUM DEPTH OF 500mm AND TO A WIDTH OF 500mm BEYOND THE FOUNDATION LIMIT OR SPECIFIED BY THE ENGINEER
- MATERIAL SPECIFICATION:**
- | 1. CONCRETE | CLASS | CHARACTERISTIC STRENGTH (MPa) | MIN CEMENTITIOUS CONTENTS |
|---------------------|-------|-------------------------------|---------------------------|
| (1) BLINDING LAYER | 15/20 | 15 | |
| (2) SLABS AND WALLS | 30/20 | 30 | 300 kg/m ³ |
- | 2. REINFORCEMENT | TYPE | YIELD STRENGTH (MPa) | MIN RADIUS |
|---------------------------------|------|----------------------|------------|
| (1) MILD STEEL BARS (R) | | 250 | 2 x DIAM |
| (2) HIGH TENSILE STEEL BARS (Y) | | 450 | 3 x DIAM |
- CONSTRUCTION:**
- ALL EXPOSED SHARP EDGES TO HAVE 20 x 20mm CHAMFERS.
 - CONCRETE COVER TO REINFORCING: 50mm FOR ALL STRUCTURAL ELEMENTS. 75mm ELSEWHERE
 - CONCRETE FINISH:
 - NON-VISIBLE SURFACES - F1
 - VISIBLE SURFACES - F2
 - UNFORMED SURFACES - U2
 - STRUCTURE NUMBER TO BE INSCRIBED ON OUTSIDE FACE OF HEADWALL AS PER DETAIL WCS/60/4/D1
 - HEADWALL TO BE 50mm ABOVE THE FILL SLOPE AND NOT MORE THAN 50mm ABOVE THE SHOULDER BREAK POINT.
- THIS DRAWING TO BE READ IN CONJUNCTION WITH SECTION 2200 OF THE COLTO DOCUMENT "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE WORKS FOR STATE ROAD AUTHORITIES".

NO.	DATE	ADDITIONS AND AMENDMENTS	DESIGNED BY:	MNCEDI OJI
VI	12/12/19		CHECKED BY:	WESSEL LOURENS
			DRAWN BY:	MNCEDI OJI
			CHECKED BY:	WESSEL LOURENS



WESTERN CAPE GOVERNMENT
DEPARTMENT OF TRANSPORT AND PUBLIC WORKS

PROJECT DESIGN CO-ORDINATOR
DATE: _____

APPROVED
THIS APPROVAL IS FOR PROCEDURAL AND ADMINISTRATIVE REVIEW PURPOSES ONLY AND DOES NOT ATTRACT LEGAL LIABILITY OF ANY KIND FROM WHATSOEVER OR HOWEVER ARISING

PROVINCIAL ROADS ENGINEER
DATE: _____

PROPOSED EXTENSION OF CULVERT 10473 ON MAIN ROAD 201 AT KM 59,056 WILDEPERDEJAG RIVER

GENERAL ARRANGEMENT

P.R.E.'s FILE No.	SCALE
TPW 16/6/4/14 - MR0201	AS SHOWN
CONTRACT No.	WCG STRUCTURE PLAN No.
C1120	10473-02
ORIGINAL PAPER SIZE.	WCG INDEX No.
A0	A93/669